

工程预算表

工程名称：Partisi Workshop 5 & 6 车间 5 & 6 隔断施工

Contractor(施工厂商)：PT. MODERN JAYA KONSTRUKSI

No.	Description 明细	Brand/spek 品牌/规格	单位	BOQ FINAL		
				内容		
				quantity/数量	price单价	total/总价
I	PEKERJAAN PERSIAPAN 准备工作					
1	Mob dan Demobilisasi 设备及人员进出场		lot	1.00	12,500,000	12,500,000
2	Alat Bantu Pekerjaan 施工辅助工具		lot	1.00	59,493,114	59,493,114
3	Safety 安全措施		lot	1.00	10,000,000	10,000,000
	SUBTOTAL PEKERJAAN PERSIAPAN 准备工作					81,993,114
II	PARTISI WORKSHOP 5 车间 5 隔断施工					
A	PARTISI ALUMUNIUM KACA 铝合金玻璃隔断					
A.1	Gudang 仓库 (P. 7,06 x L. 5 x T. 3)m					
1	Partisi Aluminium (silver) 3", Spandrell dan Kaca Polos 5mm, 3" 银色铝合金隔断 · 带 Spandrell 和 5mm 透明玻璃	Inkalume/Mulia/setara	m2	31.30	715,000	22,379,214
2	Pintu Swing Double Aluminium, uk. 150 x 214 cm 铝合金双开平开门 · 尺寸. 150 x 214 cm		unit	1.00	3,845,000	3,845,000
	spek :					
	- Aluminium 3" (silver) 银色铝合金	Inkalume/setara				
	- Kaca Polos 透明玻璃	Mulia/setara				
	- Accessories 配件	Dekson/Orca				
	- Door Closer 闭门器	Dekson/Orca	unit	2.00	600,000	1,200,000
3	Jendela Sliding Aluminium, uk. 144 x 116 cm 铝合金推拉窗 · 尺寸144 x 116 cm		unit	1.00	2,000,000	2,000,000
	spek :					
	- Aluminium 3" (silver) 银色铝合金	Inkalume/setara				
	- Kaca Polos 透明玻璃	Mulia/setara				
	- Accessories 配件	Dekson/Orca				
A.2	Ruang Inspeksi 1 检验室 1 (P. 7,06 x L. 4 x T. 3)m					
1	Partisi Aluminium (silver) 3", Spandrell dan Kaca Polos 5mm, 3" 银色铝合金隔断 · 带 Spandrell 和 5mm 透明玻璃	Inkalume/Mulia/setara	m2	31.30	715,000	22,379,214
2	Pintu Swing Double Aluminium, uk. 150 x 214 cm 铝合金双开平开门 · 尺寸. 150 x 214 cm		unit	1.00	3,845,000	3,845,000
	spek :					
	- Aluminium 3" (silver) 银色铝合金	Inkalume/setara				
	- Kaca Polos 透明玻璃	Mulia/setara				
	- Accessories 配件	Dekson/Orca				
	- Door Closer 闭门器	Dekson/Orca	unit	2.00	600,000	1,200,000
3	Jendela Sliding Aluminium, uk. 144 x 116 cm 铝合金推拉窗 · 尺寸144 x 116 cm		unit	1.00	2,000,000	2,000,000
	spek :					
	- Aluminium 3" (silver) 银色铝合金	Inkalume/setara				
	- Kaca Polos 透明玻璃	Mulia/setara				
	- Accessories 配件	Dekson/Orca				
A.3	Ruang Inspeksi 2 检验室 2 (P. 7,06 x L. 4 x T. 3)m					
1	Partisi Aluminium (silver) 3", Spandrell dan Kaca Polos 5mm, 3" 银色铝合金隔断 · 带 Spandrell 和 5mm 透明玻璃	Inkalume/Mulia/setara	m2	31.30	715,000	22,379,214
2	Pintu Swing Double Aluminium, uk. 150 x 214 cm 铝合金双开平开门 · 尺寸. 150 x 214 cm		unit	1.00	3,845,000	3,845,000
	spek :					
	- Aluminium 3" (silver) 银色铝合金	Inkalume/setara				
	- Kaca Polos 透明玻璃	Mulia/setara				
	- Accessories 配件	Dekson/Orca				
	- Door Closer 闭门器	Dekson/Orca	unit	2.00	600,000	1,200,000
3	Jendela Sliding Aluminium, uk. 144 x 116 cm 铝合金推拉窗 · 尺寸144 x 116 cm		unit	1.00	2,000,000	2,000,000
	spek :					
	- Aluminium 3" (silver) 银色铝合金	Inkalume/setara				
	- Kaca Polos 透明玻璃	Mulia/setara				
	- Accessories 配件	Dekson/Orca				
A.5	Kantor Barang Jadi 成品办公室 (P. 7,06 x L. 5 x T. 3)m					
1	Partisi Aluminium (silver) 3", Spandrell dan Kaca Polos 5mm, 3" 银色铝合金隔断 · 带 Spandrell 和 5mm 透明玻璃	Inkalume/Mulia/setara	m2	28.98	715,000	20,720,700
2	Pintu Swing Single Aluminium, uk. 120 x 214 cm 铝合金单开平开门 · 尺寸 120 x 214 cm		unit	2.00	3,076,000	6,152,000
	spek :					
	- Aluminium 3" (silver) 银色铝合金	Inkalume/setara				
	- Kaca Polos 透明玻璃	Mulia/setara				
	- Accessories 配件	Dekson/Orca				
	- Door Closer 闭门器	Dekson/Orca	unit	2.00	600,000	1,200,000
3	Jendela Sliding Aluminium, uk. 144 x 116 cm 铝合金推拉窗 · 尺寸144 x 116 cm		unit	1.00	2,000,000	2,000,000
	spek :					
	- Aluminium 3" (silver) 银色铝合金	Inkalume/setara				
	- Kaca Polos 透明玻璃	Mulia/setara				
	- Accessories 配件	Dekson/Orca				
	SUBTOTAL PARTISI ALUMUNIUM KACA 铝合金玻璃隔断					118,345,342
B	PEKERJAAN PLAFOND 天花板施工					
1	Supprot Rangka Perkuatan Dinding, Klem H Beam +Kawat Seling 2mm+Longdrat 墙体加固支架 · H型钢夹具 + 2mm钢丝绳 + 全螺纹螺栓	LS/setara	m2	5,400.00	160,000	864,000,000
2	Pas. CNP 100 x 2,3mm dan hollow 40x40x2mm 安装	LS/setara	m2	127.08	390,000	49,561,200
3	fungsi : untuk kekuatan dinding partisi dan plafond 用于隔断墙及天花板加固					
	Plafond Gyptile + Rangka, Gyptile 天花板及龙骨架	Jayapanel/setara	m2	5,527.08	140,000	773,791,200
	SUBTOTAL PEKERJAAN PLAFOND 天花板施工					1,687,352,400
C	PEKERJAAN KELISTRIKAN 电气工程					
1	Kabel NYY 4x4mm, Power dari Panel Untuk Office 办公区域电源电缆	Jembo/Eterma/setara	m	180.00	70,000	12,600,000
2	Kabel NYY 3x4mm, Stop Kontak AC 空调插座电缆	Jembo/Eterma/setara	m	36.00	68,000	2,448,000
3	Kabel NYM 3x2.5mm, Stop Kontak & Saklar 插座与开关电缆	Jembo/Eterma/setara	m	144.00	40,000	5,760,000

				BOQ FINAL		
No.	Description 明细	Brand/spek 品牌/规格	单位	内容		
				quantity/数量	price单价	total/总价
4	Kabel NYM 2x2.5mm, Lampu 灯具电缆	Jembo/Eterma/setara	m	56.00	28,000	1,568,000
5	Pipa Conduit 20 - 25 mm 电缆管	Boss/PVC	m	1,195.00	15,000	17,925,000
6	Lampu Panel LED 30x120mm, 48 Watt 面板灯具	Taiwan/setara	pcs	8.00	550,000	4,400,000
7	Saklar Double 开关2孔	Panasonic/setara	pcs	4.00	110,000	440,000
8	Stop Kontak 插座	Panasonic/setara	pcs	8.00	150,000	1,200,000
9	Stop kontak AC 空调插座	Panasonic/setara	pcs	3.00	175,000	525,000
10	Pipa Refrigerant 3/8" dan 3/4" 制冷管	Hoda/setara	m	50.00	250,000	12,500,000
11	Pas. AC Split 2 PK, Unit+Outdoor, Bracket 安装分体空调 2 PK, 室内机+室外机, 支架	Gree	unit	3.00	12,000,000	36,000,000
12	Pipa Refrigerant 1/4" dan 3/8" 制冷管	Hoda/setara	m	10.00	150,000	1,500,000
13	Box Panel 60x50x25 配电箱	Indoor	unit	1.00	8,500,000	8,500,000
14	Box Heager 6 Group 海格箱	Presto	pcs	4.00	150,000	600,000
15	MCCB 3P 50 A 开关	Schneiders/setara	pcs	1.00	750,000	750,000
16	MCB 3P 25 A 开关	Schneiders/setara	pcs	4.00	550,000	2,200,000
17	MCB 1P 16 A 开关	Schneiders/setara	pcs	11.00	250,000	2,750,000
18	MCB 1P 10 A 开关	Schneiders/setara	pcs	4.00	225,000	900,000
19	MCB 1P 6 A 开关	Schneiders/setara	pcs	4.00	215,000	860,000
20	Tray Kabel Galvaniz uk. 200x50 + Tanpa Cover + Fitting 无盖电缆桥架及连接配件		m	16.00	350,000	5,600,000
	SUBTOTAL PEKERJAAN KELISTRIKAN 电气工程					119,026,000
	SUBTOTAL PARTISI WORKSHOP 5 车间 5 隔断施工					1,924,723,742
III	PARTISI WORKSHOP 6 车间 6 隔断施工					
A	PARTISI ALUMUNIUM KACA 铝合金玻璃隔断					
A.1	KANTOR 办公室 (P. 12 x L. 8 x T. 3)m					
1	Partisi Aluminium (silver) 3", Spandrell dan Kaca Polos 5mm, 3" 银色铝合金隔断 · 带 Spandrell 和 5mm 透明玻璃	Inkalume/Mulia/setara	m2	50.16	715,000	35,864,400
2	Pintu Swing Double Aluminium, uk. 150 x 214 cm 铝合金双开平开门 · 尺寸. 150 x 214 cm		unit	2.00	3,845,000	7,690,000
	spek :					
	- Aluminium 3" (silver) 银色铝合金	Inkalume/setara				
	- Kaca Polos 透明玻璃	Mulia/setara				
	- Accessories 配件	Dekson/Orca				
	- Door Closer 闭门器	Dekson/Orca	unit	4.00	600,000	2,400,000
3	Jendela Sliding Aluminium, uk. 144 x 116 cm 铝合金推拉窗 · 尺寸144 x 116 cm		unit	2.00	2,000,000	4,000,000
	spek :					
	- Aluminium 3" (silver) 银色铝合金	Inkalume/setara				
	- Kaca Polos 透明玻璃	Mulia/setara				
	- Accessories 配件	Dekson/Orca				
A.2	Gudang 仓库 (P. 6 x L. 4 x T. 3)m					
1	Partisi Aluminium (silver) 3", Spandrell dan Kaca Polos 5mm, 3" 银色铝合金隔断 · 带 Spandrell 和 5mm 透明玻璃	Inkalume/Mulia/setara	m2	23.45	715,000	16,766,178
2	Pintu Swing Double Aluminium, uk. 150 x 214 cm 铝合金双开平开门 · 尺寸. 150 x 214 cm		unit	1.00	3,845,000	3,845,000
	spek :					
	- Aluminium 3" (silver) 银色铝合金	Inkalume/setara				
	- Kaca Polos 透明玻璃	Mulia/setara				
	- Accessories 配件	Dekson/Orca				
	- Door Closer 闭门器	Dekson/Orca	unit	2.00	600,000	1,200,000
3	Jendela Sliding Aluminium, uk. 144 x 116 cm 铝合金推拉窗 · 尺寸144 x 116 cm		unit	2.00	2,000,000	4,000,000
	spek :					
	- Aluminium 3" (silver) 银色铝合金	Inkalume/setara				
	- Kaca Polos 透明玻璃	Mulia/setara				
	- Accessories 配件	Dekson/Orca				
A.3	RUANG QC 质检室 (质检室) (P. 6 x L. 4 x T. 3)m					
1	Partisi Aluminium (silver) 3", Spandrell dan Kaca Polos 5mm, 3" 银色铝合金隔断 · 带 Spandrell 和 5mm 透明玻璃	Inkalume/Mulia/setara	m2	25.12	715,000	17,960,514
2	Pintu Swing Double Aluminium, uk. 150 x 214 cm 铝合金双开平开门 · 尺寸. 150 x 214 cm		unit	1.00	3,845,000	3,845,000
	spek :					
	- Aluminium 3" (silver) 银色铝合金	Inkalume/setara				
	- Kaca Polos 透明玻璃	Mulia/setara				
	- Accessories 配件	Dekson/Orca				
	- Door Closer 闭门器	Dekson/Orca	unit	2.00	600,000	1,200,000
3	Jendela Sliding Aluminium, uk. 144 x 116 cm 铝合金推拉窗 · 尺寸144 x 116 cm		unit	1.00	2,000,000	2,000,000
	spek :					
	- Aluminium 3" (silver) 银色铝合金	Inkalume/setara				
	- Kaca Polos 透明玻璃	Mulia/setara				
	- Accessories 配件	Dekson/Orca				
	SUBTOTAL PARTISI ALUMUNIUM KACA 铝合金玻璃隔断					100,771,092
B	PEKERJAAN PLAFOND 天花板施工					
1	Supprot Rangka Perkuatan Dinding, Klem H Beam +Kawat Seling 2mm+Longdrat 墙体加固支架 · H型钢夹具 + 2mm钢丝绳 + 全螺纹螺杆	LS/setara	m2	5,400.00	160,000	864,000,000
2	Pas. CNP 100 x 2,3mm dan hollow 40x40x2mm 安装	LS/setara	m2	144.00	390,000	56,160,000
	fungsi : untuk perkuatan dinding partisi dan plafond 用于隔断墙及天花板加固					
3	Plafond Gyptile + Rangka, Gyptile 天花板及龙骨架	Jayapanel/setara	m2	5,544.00	140,000	776,160,000
	SUBTOTAL PEKERJAAN PLAFOND 天花板施工					1,696,320,000
C	PEKERJAAN KELISTRIKAN 电气工程					
1	Kabel NYY 4x4mm, Power dari Panel Untuk Office 办公区域电源电缆	Jembo/Eterma/setara	m	135.00	70,000	9,450,000
2	Kabel NYY 3x4mm, Stop Kontak AC 空调插座电缆	Jembo/Eterma/setara	m	36.00	68,000	2,448,000
3	Kabel NYM 3x2.5mm, Stop Kontak & Saklar 插座与开关电缆	Jembo/Eterma/setara	m	132.00	40,000	5,280,000
4	Kabel NYM 2x2.5mm, Lampu 灯具电缆	Jembo/Eterma/setara	m	84.00	28,000	2,352,000
5	Pipa Conduit 20 - 25 mm 电缆管	Boss/PVC	m	1,171.00	15,000	17,565,000
6	Lampu Panel LED 30x120mm, 48 Watt 面板灯具	Taiwan/setara	pcs	12.00	550,000	6,600,000
7	Saklar Double 开关2孔	Panasonic/setara	pcs	3.00	110,000	330,000
8	Stop Kontak 插座	Panasonic/setara	pcs	8.00	150,000	1,200,000
9	Stop kontak AC 空调插座	Panasonic/setara	pcs	3.00	175,000	525,000

No.	Description 明细	Brand/spek 品牌/规格	单位	BOQ FINAL		
				内容		
				quantity/数量	price单价	total/总价
10	Pipa Refrigerant 3/8" dan 3/4" 制冷管	Hoda/setara	m	50.00	250,000	12,500,000
11	Pas. AC Split 2 PK, Unit+Outdoor, Bracket 安装分体空调 2 PK, 室内机+室外机, 支架	Gree	unit	3.00	12,000,000	36,000,000
12	Pipa Refrigerant 1/4" dan 3/8" 制冷管	Hoda/setara	m	10.00	150,000	1,500,000
13	Box Panel 60x50x25 配电箱	Indoor	unit	1.00	8,500,000	8,500,000
14	Box Heager 6 Group 海格箱	Presto	pcs	3.00	150,000	450,000
15	MCCB 3P 50 A 开关	Schneiders/setara	pcs	1.00	750,000	750,000
16	MCB 3P 25 A 开关	Schneiders/setara	pcs	3.00	550,000	1,650,000
17	MCB 1P 16 A 开关	Schneiders/setara	pcs	11.00	250,000	2,750,000
18	MCB 1P 10 A 开关	Schneiders/setara	pcs	3.00	225,000	675,000
19	MCB 1P 6 A 开关	Schneiders/setara	pcs	3.00	215,000	645,000
20	Tray Kabel Galvaniz uk. 200x50 + Tanpa Cover + Fitting 无盖电缆桥架及连接配件		m	16.00	350,000	5,600,000
	SUBTOTAL PEKERJAAN KELISTRIKAN 电气工程					116,770,000
	SUBTOTAL PARTISI WORKSHOP 6 车间6 隔断施工					1,913,861,092
IV	PARTISI KAWAT RAM WORKSHOP 4 车间4铁丝网隔断工程					
A	TAHAP AWAL 初始阶段					
1	Partisi Besi Kawat Ram 铁网钢分隔墙		m2	311.95	555,000	173,132,250
	spek :					
	- Hollow 50x50x2 mm	LS/setara				
	- Siku 40x40x4 mm 角钢	LS/setara				
	- Kawat Ram 50x50x4mm 铁丝网	LS/setara				
	- CNP 100x50x2,3mm	LS/setara				
	- Kawat Ram 50x50x4mm 铁丝网	LS/setara				
	- Baseplate 3mm	LS/setara				
	- Dynabolt M12					
2	Finishing Cat Partisi Kawat 铁网分隔墙涂装	Ftalit - Kansai	m2	623.90	45,000	28,075,500
3	Pintu Single Sliding Besi uk. 200x300 cm 单开滑动门铁		unit	1.00	7,500,000	7,500,000
	spek :					
	- Hollow 50x50x2mm	LS/setara				
	- Kawat Ram 50x50x4mm 铁丝网	LS/setara				
	- Siku 40x40x4 mm 角钢	LS/setara				
	- Finishing Cat 涂装收尾	Ftalit - Kansai				
	- Aksesoris Pintu Sliding 推拉门配件					
B	TAHAP KEDUA (REQUEST OWNER) 第二阶段 (业主要求)					
1	Pembongkaran Partisi Besi Kawat Ram Area 1 拆除区域1铁丝网隔断		m2	155.80	175,000	27,265,000
2	Pembongkaran Pintu Single Sliding Besi, uk. 200x300 cm 拆除单开滑动铁门 200x300厘米		unit	1.00	350,000	350,000
3	Reinstall Partisi Kawat Ram 重新安装铁丝网隔断		m2	192.56	350,000	67,394,250
	Scoope :					
	- Kawat Las, WD, DLL					
	- Finishing Cat 涂装收尾	Ftalit - Kansai				
4	Reinstall Pintu Single Sliding Besi, uk. 200x300 cm 重新安装单开滑动铁门 200x300厘米		unit	1.00	2,100,000	2,100,000
	Scoope :					
	- Kawat Las, WD, DLL					
	- Finishing Cat 涂装收尾	Ftalit - Kansai				
C	TAHAP FINAL 最终阶段					
1	Pembongkaran Partisi Besi Kawat Ram 拆除铁丝网隔断		m2	192.56	175,000	33,697,125
2	Pembongkaran Pintu Single Sliding Besi (P1), uk. 200x300 cm 拆除单开滑动铁门 (P1) 200x300厘米		unit	1.00	350,000	350,000
	SUBTOTAL PARTISI KAWAT RAM WORKSHOP 4 车间4铁丝网隔断工程					339,864,125
	Total Perhitungan/ 合计					4,260,442,073
1、已含PPH%，不含11%增值税						
2、已含整套竣工图纸						

甲方代表人 PIHAK PERTAMA Perwakilan

乙方代表人 PIHAK KEDUA Perwakilan

