

工程预算表

工程名称 : Pekerjaan Jalan Keluar Dari Parkiran 停车场出口道路工程

Contractor(施工厂商) : PT MODERN JAYA KONSTRUKSI

No.	Description 明细	单位	内容				Brand/spek 品牌/规格
			quantity/数量	材料	人工安装	total/总价	
A	PEKERJAAN PERSIAPAN 准备工作						
1	Mob dan Demobilisasi 进场与撤场	lot	1.00		7,000,000	7,000,000	
2	Safety / 安全 Cleaning / 清洁	lot	1.00		2,000,000	2,000,000	
3	Pekerjaan Bouwplank 水准桩施工	m	194.71	23,000	20,000	8,372,358	
	SUBTOTAL PEKERJAAN PERSIAPAN 准备工作					17,372,358	
B	PEKERJAAN SALURAN BOX CULVERT 箱涵排水工程						
1	Galian Tanah 土方开挖	m3	28.99		65,000	1,884,415	
2	Pengurugan tanah kembali 土方回填	m3	9.66		42,000	405,874	
3	Buang Galian Tanah 弃土外运	m3	19.33		42,000	811,748	
4	Pemasangan Box Culvert 1500 x 1500mm 箱涵安装	m	8.13	9,500,000	850,000	84,145,500	
5	Pemasangan Box Culvert 800 x 800mm 箱涵安装	m	8.00	3,000,000	350,000	26,800,000	
	SUBTOTAL PEKERJAAN SALURAN BOX CULVERT 箱涵排水工程					114,047,537	
C	PEKERJAAN STRUKTUR JALAN 道路结构工程						
C.1	PEKERJAAN BATU KALI/BATU BELAH 河石/碎石作品						
1	Pemasangan Cerucuk Bambu 竹桩施工安装	m	438.09	23,000	11,000	14,895,009	
2	Galian Tanah 土方开挖	m3	48.68		65,000	3,163,973	
3	Pengurugan tanah kembali 土方回填	m3	16.23		42,000	681,471	
4	Pasangan Batu Kali 河石砌体	m3	82.17	855,000	260,000	91,615,014	
C.2	PEKERJAAN TIMBUNAN 打包工作						
1	Pasir Urugan t=10cm 回填砂	m3	72.04	465,000	70,000	38,542,053	
2	Makadam 5x7 t=20cm 碎石路	m3	144.08	495,000	200,000	100,137,296	
3	Basecourse t = 10cm 基层厚度 = 10厘米	m3	72.04	410,000	135,000	39,262,465	
4	Pemadatan Basecourse 基层压实	m2	720.41		20,000	14,408,244	

No.	Description 明细	单位	内容				Brand/spek 品牌/规格
			quantity/数量	材料	人工安装	total/总价	
C.3	PEKERJAAN ASPAL JALAN 道路沥青施工						
1	Pekerjaan Lapisan Primer/Tack Coat 底油 / 黏层施工	m2	720.41	21,000	8,000	20,891,954	
2	Hotmix Aspal t = 3cm 单层热拌沥青	m2	720.41	75,000		54,030,915	
3	Pemadatan dan Perataan Perlapisan Aspal 沥青层压实及整平	m2	720.41		25,000	18,010,305	
	SUBTOTAL PEKERJAAN STRUKTUR JALAN 道路结构工程					395,638,698	
	Total Perhitungan / 合计					527,058,593	
	Pembulatan / 取整				-	58,593	
	Grand Total / 总价					527,000,000	

甲方代表人 PIHAK PERTAMA Perwakilan

乙方代表人 PIHAK KEDUA Perwakilan

